

**SURVEY & REMONUMENTATION**

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**

94 NOV 28 AM 11:49

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

**COMMISSION**

*Leif J. Bond*  
REG. OF DEEDS

For corners in KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>12W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**7345**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William R. Byl, in a field survey on May 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-11	1837	GLO	Whitcomb	Set Post
		City of Grand Rapids		City Iron
	1962	Kent Co. Wit.	MDSH	City Iron
	1981	LCRC #2030	Hackbardt	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 6/9/81 and was recorded per LCRC #2030.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt in place of the City Iron he found. Said City Iron checks with Kent Co. Wit. & City of Grand Rapids records.

LCRC #2030

N. leg of tower	N80°W	70.00'
S. leg of tower	S85°W	62.15'
KC Nail & tag W. side 20" Oak	N10°E	62.95'
KC Nail & tag W. side 14" Oak	N30°E	72.45'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN *Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-11 Standard Kent County Monument

N. leg of tower	N80°W	70.00'
S. leg of tower	S85°W	62.15'
New KC Nail & tag W. side 24" Oak	N10°E	62.87'
New KC Nail & tag W. side 18" Oak	N30°E	72.47'



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 11-17-94