

\$7.00  
\$2.00

JAN 24 1996 KENT COUNTY REMONUMENTATION  
COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	7N	R	12W	J-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

REG. OF DEEDS

*Handwritten signature*

95 DEC 26 PM 12:42

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

8848

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Nov. 15, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- J-6 1837 GLO Not Set
- 1908 City of Grand Rapids City Iron
- "X" in wk. SW 42.10' MH S. 32.38' PBM SSE 43.52'
- "X" in wk. SE 45.16' Hse. Cor. SE 75.12' MH E. 31.68'
- 1928-55 Williams & Works City Iron
- KC Wit. City Iron (14" Oak NE 51.6'-Cor. H. SE 75.2'-T.P. SW 32.0')
- 1993 Exxel Eng. City Iron
- P. Pole NNW 83.70' Util. Pole SW 31.35'
- Center of Hydt. ENE 42.48' NW cor. brick wall hse. SE 75.94'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-6 Found City Iron that fits remaining witnesses from those above. Said City Iron is 2.6' W. & 3.4' S. from true intersection of 1/4 lines.

The City Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN *Handwritten signature*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-6 Set Standard Kent County Monument in place of the City Iron
- NE corner brick chimney S60°W 77.81'
- Set Nail & KC Remon. tag E. side P. Pole N20°W 93.69'
- C/L top fire hydrant N70°E 47.93' (newer hydr.)
- NW cor. brick wall W. side Hse. #1156 S50°E 75.94'
- City Bench Mark S50°E 43.62'
- C/L Manhole S00°E 33.60'
- C/L Manhole S90°E 32.70'

Signed by

*Handwritten signature*

Date

12/14/95

Surveyor's Michigan License No.

30077

