

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 NOV 28 AM 11:49

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>7N</u> R <u>12W</u> | <u>K-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Lucy Bond
REG. OF DEEDS

7356

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on March 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2	1837	GLO	Whitcomb	Set Post	P.A. 345 1990 KENT COUNTY
	1960	Kent Co. Wit.	MDSH	Iron	PEER APPROVED <u>11/17/94</u>
	1973	LCRC #524	Spicer	3/4" Iron in Mon. Box	CHAIRMAN <i>Harry Huber</i>
	1981	LCRC #1853	Tobin	Set Kent County Monument	
	1992	LCRC #6487	McCloskey	Kent County Monument	
	1992	LCRC #6641	McCloskey	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas J. Tobin on 2/26/81 and was recorded per LCRC #1853

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas J. Tobin in place of the 3/4" Iron he found in a Mon. Box. Said 3/4" Iron in Mon. Box checks with LCRC #524.

<u>LCRC #1853</u>		<u>LCRC #6641</u>	
NW cor. CB header	N50°W 62.20'	NW cor. CB header	N48°W 62.23'
Top C/L hydrant	N30°W 148.52'	Top centerline hydrant	N22°W 148.50'
Mon. rest near E. edge of center lane of Southbound lane pavement		Face of curb	West 49.22'
		Nail & Tag Util. Pole	S26°E 105.84'
		Nail & Tag Util. Pole	N34°E 102.54'
		Top C/L E. bolt Lt. Pole	N52°W 83.73'
		PK in walk joint	N86°E 50.39'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Standard Kent County Monument	
NW corner C.B. header	N48°W 62.20'
Top C/L hydrant	N22°W 148.50'
Face of curb	S90°W 49.22'
Set nail & KC Remon. tag NE side Utility Pole	S26°E 105.94'
Set nail & KC Remon. tag NE side Utility Pole	N34°E 102.40'
Top C/L E. bolt to Light Pole	N52°W 83.64'
PK in walk joint	N86°E 50.39'



Signed by *William R. Byl* Date 11-17-94

Surveyor's Michigan License No. 23502