

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
9/11 NOV 28 AM 11:50

For corners in **COMMISSION**
KENT COUNTY
(County)

Located In:	Corner Code #
1. Public Land Survey T <u>7N</u> R <u>12W</u>	<u>K-8</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
2. Property Controlling S _____ T _____ R _____	_____
in Section S _____ T _____ R _____	_____
3. Miscellaneous S _____ T _____ R _____	_____
Property in Sec. S _____ T _____ R _____	_____

Lucy Bond
REG. OF DEEDS

7362

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Sept. 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8	1837	GLO	Whitcomb	Set Post
			City of Grand Rapids	City Iron
	1980	LCRC #1331	Byl	City Iron
	1982	LCRC #2803	Merdzinski	City Iron

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented (left City Iron in place) by John A. Merdzinski on 3/19/82 and was recorded per LCRC #2803

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 **FOUND NOTHING AT CORNER.** Corner was removed during road and sewer construction Spring-Summer 1994. Set point per witnesses from above LCRC as used by John A. Merdzinski for the City Iron he found. Said point checks with City of Grand Rapids information and LCRC #1331.

LCRC #2803

NE corner frame bldg.	S30°E	39.03'	P.A. 345 1990 KENT COUNTY
NW corner foundation of frame bldg.	S10°W	33.11'	PEER APPROVED 11/17/94
SE corner brick bldg.	S50°W	77.05'	CHAIRMAN <i>Harry Huber</i>
SE corner bottom step to Hse. #803	N40°W	55.20'	
SW corner conc. blk. bldg.	N30°E	69.25'	

Corner is On C/L Alpine Ave running North and on C/L 7th St. running E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Grouted yellow "KENT COUNTY REMON." cap at corner as described in "B" above next to rim of manhole.

NE corner frame bldg.	S30°E	38.9' m/1
NW corner foundation of frame bldg.	S10°W	33.11'
SE corner brick bldg.	S50°W	77.05'
SE corner bottom step to Hse. #803	N40°W	55.20'
SW corner conc. blk. bldg.	N30°E	69.25'

E'ly edge of manhole rim is WSW'ly 0.12'

Corner is On C/L Alpine Ave running North and on C/L 7th St. running E-W



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11-17-94