

\$7.00
\$2.00

JAN 24 1996

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 7N | R | 12W | L-2 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous | S | | T | R | |
| Property in Section | S | | T | R | |

REG. OF DEEDS

Lucy St. Paul

95 DEC 26 PM 12:42

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8833

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Nov. 15, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|-----|---------|--|---|
| L-2 | 1837 | GLO | Not Set |
| | 1894 | Williams & Works | Stake & Stone |
| | 1912 | Williams & Works | 2" Pipe |
| | 1950-64 | Williams & Works | Concrete Monument ("Center" of Sec. 1 per "Green Ridge" Liber 47, Pg. 6 1950) |
| | | Tw. Oak 36" N. 17.95' 30" Oak SW 16.12' Tw. Oak 8" S. 22.38' | |
| | | Exxel Eng. | "Plat Monument" at Center |
| | 1989 | Prien & Newhof | Concrete Monument |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-2 Found Concrete Monument that fits remaining witnesses of those above and fits other irons and monuments in "Green Ridge." Said Concrete Monument is 1.8' N. & 2.5' W. from true intersection of 1/4 lines.

The Concrete Monument is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN *Harry Hubert*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-2 Set Standard Kent County Monument in place of the Concrete Monument.

- | | | |
|--|-------|--------|
| Set Nail & KC Remon. tag E. side Tw. 32" Oak | N10°E | 18.24' |
| Set Nail & KC Remon. tag S. side 24" Oak | S60°E | 15.21' |
| Set Nail & KC Remon. tag SE side 30" Cherry | S40°W | 14.56' |
| Set Nail & KC Remon. tag W. side 30" Oak | S20°E | 38.12' |
| Capped Iron (Exxel) | S00°W | 20.12' |
| Concrete Monument | N90°E | 70.75' |



Signed by *Kirk Breitels*

Date 12/14/95

Surveyor's Michigan License No. 30077