

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 NOV 28 AM 11:51

COMMISSION

For corners in
KENT COUNTY

(County)	Located In:	Corner Code -#
1. Public Land Survey	T <u>7N</u> R <u>12W</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

W. R. Byl
REG. OF DEEDS

7381

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on May 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-9	1837	GLO	Lyon	Set Post
		City of Grand Rapids		City Iron
	1973	LCRC #518	Spicer	PK Nail
	1982	LCRC #3110	Merdzinski	PK Nail & Remon. tag over City Iron

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/13/82 and was recorded per LCRC #3110.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found short Rerod and "Kent Co. Remon." cap per witnesses from above LCRC as used by John A. Merdzinski when he set PK Nail & Remon. tag over top of City Iron which he found. Said City Iron checks with LCRC #518. Short Rerod and "Kent Co. Remon." cap was set by William R. Byl, 1985, in place of a broken PK nail which he found. Said broken PK nail checks with LCRC #518 & #3110.

LCRC #3110

NW cor. stone building	S32°E	61.61'
NE cor. concrete guard rail	S32°W	43.50'
SE cor. concrete guard rail	N38°W	50.73'
West edge Manhole rim	East	0.52'

Corner is on C/L Michigan St. E-W and C/L Division Ave. S.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

P.A. 345 1990 KENT COUNTY


PEER APPROVED 11/17/94

CHAIRMAN *Harold Stuber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Rerod and "Kent County Remon." cap		
NW cor. stone building	S32°E	61.61'
NE cor. concrete guard rail	S32°W	43.46'
SE cor. concrete guard rail	N38°W	50.67'
West edge Manhole rim	East	0.52'
"V" cut SW face Lt. Pole	N45°E	51.44'

Corner is on C/L Michigan St. E-W and C/L Division Ave. S.



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11-17-94