

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent
(County)

Located in: Grattan
Township

Corner Code #

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>8N</u> R <u>9W</u> | <u>A-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on July 1 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Witness Map	K.C. Surveyor	Iron
	1971	L.C.R.C. #71	Williams & Works	1" Iron (M-4, T8N, R10W)
	1978	L.C.R.C. #1177	Medema, Van Kooten & Assoc.	3/4" Iron
	1981	L.C.R.C. #1900	Jonker Land Surveys	Fnd. 1" Iron / Set K.C. Monument (M-4, T8N, R10W)
	1989	L.C.R.C. #5289	J. Bueche	K.C. Monument (M-4, T8N, R10W)

Note: This corner is common with M-4, T8N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 7/15/81 and was recorded per L.C.R.C. #1900.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 Found a Standard Kent County Monument at the C/L intersection of Tiffany Avenue (gravel) running North and South and Whitten Road (gravel) running East per L.C.R.C.'s #1900 and #5289 as set by Rob Jonker in place of a 1" iron he found which checked L.C.R.C.'s #1177, #71, and the K.C. Surveyor's records.

L.C.R.C. #1900

- Remon. tag on E side 24" Oak N 20° E 97.42'
- Remon. tag on SE side 6" Pine N 60° E 73.54'
- Remon. tag on S side 9" Oak N 88° E 154.39'
- C/L S. leg traffic sign S 80° W 17.2'

L.C.R.C. #5289

- Remon. tag & nail on E side 26" Oak N 20° E 97.35'
- Remon. tag & nail on SE side 8" Pine N 60° E 73.65'
- Remon. tag & nail on S side 12" Oak N 88° E 154.39'
- E. face S. leg of sign S 90° W 19.84'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 Standard Kent County Monument

- Nail & K.C. remon. tag on E side 26" Oak N 20° E 97.35'
- Nail & K.C. remon. tag on SE side 8" Pine N 60° E 73.65'
- Nail & K.C. remon. tag on S side 12" Oak N 88° E 154.39'
- East face South leg of sign S 90° W 19.84'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 8/28/97

CHAIRMAN [Signature]

Signed by Randy J. Kolehouse Date 9/23/97
EARTH TECH

Surveyor's Michigan License No. 25854

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 NOV 14 AM 9:00
REG. OF DEEDS
[Signature]
10298
Register of Deeds Stamp & File Number

