

**SURVEY & REMONUMENTATION**

YEAR 08 1999

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

**SECTION**

Kent (County)	Located in:	Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>9W</u>	<u>B-1</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	<u>Sec. 1</u>
	S _____	T _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____	_____
	S _____	T _____	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 98 OCT 23 AM 9:58  
 REG. OF DEEDS  
*David J. ...*

**10825**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on February 5 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B-1 This corner was not originally set by the G.L.O.

N/A	Witness Map	K.C. Surveyor	3/4" Iron
1978	L.C.R.C. #1122	Williams & Works	3/4" Iron
1978	L.C.R.C. #1205	Nederveld & Jonker	3/4" Round Iron
1980	L.C.R.C. #1731	Williams & Works	Fnd. 3/4" Iron Pipe / Set K.C. Monument (B-13, T9N, R9W)

Note: This corner is common with B-13, T9N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works 12/23/80 and was recorded per L.C.R.C. 1731.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 Found a Standard Kent County Monument 6' South of the C/L of 10 Mile Road (bit.) running East and West and 5' East of the C/L of Greenland (gravel) running North per L.C.R.C. #1731 as set by Williams & Works in place of a 3/4" iron pipe they found which checked L.C.R.C.'s #1205, #1122 and the K.C. Surveyor's records.

L.C.R.C. #1731

- K.C. Remon. Tag & Nail in N. Side P. Pole S 65°E 81.41'
- K.C. Remon. Tag & Nail in NW Side P. Pole S 75°W 92.29'
- K.C. Remon. Tag & Nail in S. Side Guard Post N 40°W 48.88' (m. 47.64')
- NW Cor. Hse. Fnd. S 50°E 106.14'
- NE Cor. Hse. Fnd. S 05°W 102.26'

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 6/25/98  
 CHAIRMAN [Signature]

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Standard Kent County Monument

- Nail & K.C. remon. tag on N side P. pole S 65° E 81.41'
- Nail & K.C. remon. tag on NW side P. pole S 75° W 92.29'
- Nail & K.C. remon. tag on SW side guard post N 40° W 47.64'
- NW cor. hse. fndn. S 50° E 106.14'
- NE cor. hse. fndn. S 05° W 102.26'
- C/L of bit. road running E-W, North 6.0'
- C/L of gravel road running N, West 5'

Signed by Randy J. Kolehouse Date 9-1-98

EARTH TECH

Surveyor's Michigan License No. 25854

