

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

MAR 08 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in

SECTION

<u>Kent</u> (County)	Located in: Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>9W</u>	<u>B-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
38 DEC 14 AM 8:00  
REG. OF DEEDS  
*Lucy St. Paul*

**11041**  
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on December 4 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6												
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- B-6 This corner was not originally set by the G.L.O.
- |      |                |                  |       |
|------|----------------|------------------|-------|
| 1952 | Survey Records | Williams & Works | Stone |
| 1974 | L.C.R.C. #758  | G. Fauser        | Stone |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-6 Found a pointed stone 50' ± South of a tree row running East and West on line of a tree row running South per L.C.R.C. #758. Stone is 11' ± South and 6' ± East of the intersection of 1/4 lines. Accepted stone as Center of Section.

L.C.R.C. #758

40" Elm N 08° E 30.96' (m. 31.17')

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/12/98  
CHAIRMAN Randy Kolehouse

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-6 Replaced Stone with a Standard Kent County Monument
- Nail & K.C. remon. tag on E side 4" maple S 20° W 14.56'
  - Nail & K.C. remon. tag on S side 4" Maple S 20° E 12.09
  - Nail & K.C. remon. tag on S side 8" Maple S 40° E 10.10'
  - Nail & K.C. remon. tag on E side 6" Maple N 40° E 13.37'
  - Tree row running E-W, North 50' ±
  - On tree row running South



Signed by Randy Kolehouse Date 12/5/98  
EARTH TECH

Surveyor's Michigan License No. 25854