

\$7.00  
\$2.00

MAR 6 8 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent (County)	Located in: Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>9W</u>	<u>D-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

*Lucy Standa*

98 DEC 14 AM 8:00

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10970

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	•	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on November 2 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


A. Description of original monument and accessories and/or subsequent restoration:  
D-12 This corner was not originally set by the G.L.O.  
No information was available on this corner.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/12/98  
CHAIRMAN Randy Kolehouse

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
D-12 Set a point at the intersection of 1/4 lines 20' South of a dry creek bed, 15' North of top of bank, and 110' South of the North edge of woods.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
D-12 Set a Standard Kent County Monument  
Nail & K.C. remon. tag on S Face 12" Maple N15° W 9.72'  
Nail & K.C. remon. tag on S Face 12" Oak S 90° W 14.55'  
Nail & K.C. remon. tag on E Face 9" Oak S 00° W 15.05'  
Nail & K.C. remon. tag on SE Face 12" Maple N 62° E 24.36'



Signed by Randy J. Kolehouse Date 11/18/98  
EARTH TECH

Surveyor's Michigan License No. 25854