

\$7.00
\$2.00

REMONUMENTATION

MAR 08 1959

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 DEC 14 AM 8:00
REG. OF DEEDS
Luci Stand

For corners in Kent (County) SECTION Located in: Grattan Township Corner Code #

1. Public Land Survey	T 8N	R 9W	H-13
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

10981
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 7 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1837	G.L.O. Notes	N. Brookfield	Set Post
	1964	Witness Map	K.C. Surveyor	3" Pipe
	1985	L.C.R.C. #5164	R. Kolehouse	Set K.C. Monument
	1991	L.C.R.C. #5871	William Byl	K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/29/98
CHAIRMAN *Randy Kolehouse*

Note: This corner is not common with H-1, T7N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse on 11/23/85 and was recorded per L.C.R.C. #5164.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-13 Found a Standard Kent County Monument on the C/L of 4 Mile Road (bit.) running East and West, on line of a tree row and fence line running North and South, per L.C.R.C.'s #5164 and #5871 as set by Randy Kolehouse midway between the Southwest and Southeast corners of Section 34.

L.C.R.C. #5164

L.C.R.C. #5871

Nail & K.C. Remon. tag in N. side 8" Oak S 65° W 74.00'
Nail & K.C. Remon. tag in SW side 16" Hickory N 35° W 31.75'
Nail & K.C. Remon tag in S. side 16" Hickory N 60° W 77.84'
K.C. Monument at the N 1/4 cor sec. 3 T7N R9W, East 6.38'

Nail & KC Remon. tag S. side 4-12" W. Cherry S60°E 85.08' (m. 85.11')
Nail & KC Remon. tag W. side Tw. 4" W. Cherry S15°W 26.06' (m. 26.21')
Nail & KC Remon. tag N. side 12" Oak S65°W 75.08' (m. 75.24')
Nail & KC Remon. tag SW side 20" Hickory N35°W 32.25' (m. 32.34')
Nail & KC Remon. tag S. side 28" Hickory N60°W 78.80' (m. 78.94')
Nail & KC Remon. tag W. side P. Pole S00°W 54.12' (m. 54.17')
Kent County Mon. @ N 1/4 cor. Sec. 3, T7N, R9W N90°E 6.38'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-13 Standard Kent County Monument
Nail & K.C. remon. tag on S side 4-12" W. Cherry S 60° E 85.11'
Nail & K.C. remon. tag on W side twin 4" Cherry S 15° W 26.21'
Nail & K.C. remon. tag on N side 12" Oak S 65° W 75.24'
Nail & K.C. remon. tag on SW side 20" Hickory N 35° W 32.34'
Nail & K.C. remon. tag on S side 20" Hickory N 60° W 78.94'

Nail & K.C. remon. tag on W side P. pole S 00° W 54.17'
On C/L of bit. road running E-W
On tree row and fence line running N-S
K.C. Mon., H-1, T7N, R9W, East 6.38'

Signed by Randy J. Kolehouse Date 9-30-98
EARTH TECH
Surveyor's Michigan License No. 25854

