

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

SECTION

Kent (County)	Located in:	Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>9W</u>	<u>I-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

REG. OF DEEDS

David J. Land

38 DEC 14 AM 8:00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10988

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 7 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13	Description	Notes	Surveyor	Monument
1837	G.L.O. Notes	N. Brookfield	Set Post	
1941	Witness Map	K.C. Surveyor	Concrete Monument	
1951	Notes	Williams & Works	Iron	
1986	L.C.R.C. #4362	R. Kolehouse	Fnd. 3/4" Iron in Mon. Box / Set K.C. Mon. in Mon. Box	
1991	L.C.R.C. #5882	William Byl	K.C. Monument in Mon. Box	

Note: This corner is not common with I-1, T7N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse on 11/23/85 and was recorded per L.C.R.C. #4362.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found a Standard Kent County Monument in a monument box 13' West of the C/L intersection of Lincoln Lake Road (bit.) running North and South and 4 Mile Road (bit.) running East and West per L.C.R.C.'s #4362 and #5882 as set by Randy Kolehouse in place of a 3/4" iron he found in a monument box which checked the 1951 notes of Williams & Works.

L.C.R.C. #4362
West end (back) cont. curb return N 60° W 54.05'
West end (back) conc. curb return S 55° W 53.93'
NW cor. C.B. S 35° E 70.35'
NW cor. C.B. S 75° E 83.12'
SW cor. C.B. N 75° E 82.43'

L.C.R.C. #5882
West end (back) conc. curb return N60°W 54.11'
West end (back) conc. curb return S55°W 53.97'
NW cor. C.B. S35°E 70.25'
NW cor. C.B. S75°E 83.05'
SW cor. C.B. N75°E 82.49'
Nail & KC Remon. tag N. side P. Pole N70°E 93.67' (m. 93.73')
Nail & KC Remon. tag SW side P. Pole N40°W 78.43'
NW cor. conc. blk. Slab to old school S55°E 148.29'
K.C. Monument at NE cor. Sec. 3-1-9 N90°E 13.22' (m. 13.24')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Standard Kent County Monument in a Monument Box

Nail & K.C. remon. tag on N side P. pole N 70° E 93.73'
Nail & K.C. remon. tag on SW side P. pole N 40° W 78.43'
NW cor. C.B. S 35° E 70.25'
NW cor. C.B. S 75° E 83.05'
SW cor. C.B. N 75° E 82.49'

NW cor. conc. blk. Slab to old school S 55° E 148.29'
C/L "X" of bit. roads running N-S-E-W, East 13'
K.C. Mon., I-1, T7N, R9W, N 90° E 13.24'

Signed by Randy J. Kolehouse Date 9-30-98

EARTHTECH

Surveyor's Michigan License No. 25854

