

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

SECTION

Kent (County)	Located in:	Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>9W</u>	<u>J-1</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 DEC 14 AM 8:00
REG. OF DEEDS
Lucy Bond

10989
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on January 28 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1 This corner was not originally set by the G.L.O.
1985 L.C.R.C. #4271 William Byl Set K.C. Monument
1994 L.C.R.C. #7227 Glaza & Associates K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/29/98
CHAIRMAN Harry Huber

Note: This corner is not common with J-13, T9N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 7/1/85 and was recorded per L.C.R.C. #4271.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Found a Standard Kent County Monument 600' ± South of the C/L intersection of 10 Mile Road (gravel) running East and West and Tully Avenue (gravel) running North per L.C.R.C.'s #4271 and #7227 as set by William Byl midway between the Northeast and Northwest corners of Section and on the South line of Section 35.

L.C.R.C. #4271

L.C.R.C. #7227

Nail & tag, W sd. 8" Maple N 25° E 12.35'
Nail & tag, E sd. 10" Maple S 25° E 24.22'
Kent Co. Monument @ S1/4 cor. Sec 35, 9-9, N 90° E 103.42'

Nail & K.C. remon tag in W side 10" Maple N25°E 12.35'
Nail & K.C. remon tag in E side 10" Maple S25°E 24.22'
Kent Co Mon (S1/4 cor, Sec 35, T9N, R9W) N90°E 103.42'
Nail & K.C. remon tag in E side 14" Maple S80°W 13.15'
Nail & K.C. remon tag in E side 12" Maple S40°W 32.22'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Standard Kent County Monument
Nail & K.C. remon. tag on W side 10" Maple N 25° E 12.35'
Nail & K.C. remon. tag on E side 10" Maple S 25° E 24.22'
Nail & K.C. remon. tag on E side 14" Maple S 80° W 13.15'
Nail & K.C. remon. tag on E side 12" Naoko S 49° W 32.22'
C/L "X" of gravel roads running E-W & N, South 600' ±
K.C. Mon., J-13, T9N, R9W, N 90° E 103.42'



Signed by Randy J. Kolehouse Date 9-30-98
EARTH TECH

Surveyor's Michigan License No. 25854