

SURVEY & REMONUMENTATION

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

SECTION

Kent
(County)

Located in: Grattan
Township

Corner Code #

- 1. Public Land Survey T 8N R 9W J-2
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Log 2

REG. OF DEEDS

1999 DEC 30 AM 9:54
RECEIVED PER RECORDS
STATE OF MICHIGAN
COUNTY OF KENT

11691

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on December 29 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-2 This corner was not originally set by the G.L.O.
1998 L.C.R.C. #11049 Earth Tech Set K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Earth Tech on 12/1/98 and was recorded per L.C.R.C. #11049.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-2 Found a Standard Kent County Monument per L.C.R.C. #11049 witnesses as set by Earth Tech.

L.C.R.C. #11049

- Nail & K.C. remon. tag on NE side P. pole S 50° E 394.84'
- Nail & K.C. remon. tag on E side P. pole S 10° W 223.92'
- Nail & K.C. remon. tag on S side 10" Apple Tree N 73° W 210.99'
- SE corner of most Easterly barn concrete foundation S 80° W 303.86'
- C/L of bit. road running E-W, South 4'
- Ditch running S, East 150'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/20/98
CHAIRMAN Randy Kolehouse

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-2 Reset a Standard Kent County Monument - Also Set a Monument Box

- Nail & K.C. remon. tag on NE side P. pole S 50° E 394.84'
- Nail & K.C. remon. tag on E side P. pole S 10° W 223.92'
- Nail & K.C. remon. tag on S side 10" Apple Tree N 73° W 210.99'
- SE corner of most Easterly barn concrete foundation S 80° W 303.86'
- C/L of bit. road running E-W, South 4'
- Ditch running S, East 150'

Signed by Randy J. Kolehouse
WILLIAMS & WORKS

Date 12-29-99

Surveyor's Michigan License No. 25854

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3						
3													
4	7		8		9		10		11		12		
6													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

