

\$7.00
\$2.00

MAR 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>9W</u>	<u>K-10</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

Eric J. Sand

38 DEC 14 AM 8:00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10997

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on February 5 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-10	1837	G.L.O. Notes	Cathcart	Set Post
	1984	L.C.R.C. #3760	R. Kolehouse	Set K.C. Monument
	1990	L.C.R.C. #5894	William Byl	K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN *[Signature]*

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse in February 1984 and was recorded per L.C.R.C. #5894.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 Found a Standard Kent County Monument (no cap) on the C/L of Ashley Avenue (gravel) running North and South, on line of a fence line running East, per L.C.R.C.'s #3760 and #5894 as set in 1984 by Randy Kolehouse.

L.C.R.C. #3760

L.C.R.C. #5894

Nail & K.C. Remon. tag in N. side 14" Oak East 30.75'
Nail & K.C. Remon. tag in W. side 4" Oak S 40 E 64.62'
Nail & K.C. Remon. tag in Ely side 12" maple S 30 W 70.08'
Nail & K.C. Remon. tag in SE side 42" Oak S 75 W 44.32'
Monument is in C/L Ashley Ave. (gravel) running North & South
On line of fence running East & West

Nail & KC Remon. tag N. side 18" Oak N90°E 30.75' (m. 30.80')
Nail & KC Remon. tag W. side 8" Oak S40°E 64.65'
Nail & KC Remon. tag E. side 16" maple S30°W 70.17' (m. 70.22')
Nail & KC Remon. tag SE side 48" Oak S75°W 44.32' (m. 44.37')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Replaced Cap on a Standard Kent County Monument

Nail & K.C. remon. tag on N side 18" Oak N 90° E 30.80'
Nail & K.C. remon. tag on W side 10" Oak S 40° E 64.65'
Nail & K.C. remon. tag on E side 18" Maple S 30° W 70.22'
Nail & K.C. remon. tag on SE side 48" Oak S 75° W 44.37'
Nail & K.C. remon. tag on E side 6" Oak S 78° W 39.42'
On C/L of gravel road running N-S
On fence line running E



Signed by *Randy J. Kolehouse* Date 9-30-98

EARTH TECH

Surveyor's Michigan License No. 25854