

NER 00 1989

| Forc | orners in | SECTION | Filing Require | R RECORDATION CO ment of Act 74, Mico JNTY REMONUMENT | h. P.A. 1970 | REG. | COUNT | /2 여 분 리 디 | |
|-------------------------------------|--|---|---|--|--|--|---|---|--|
| | Kent (County) | Lo | ocated in: Grattan Township | Corner Code # | | OF DEE | | Professional Control of the Control | |
| 1. È | Public Land Surve | | TR | K-13 | | in Constitution | 8: 00 | <u>.</u> | |
| | Property Controllin n Section | g s | TR TR | | | 11000 | | | |
| | Miscellaneous Property in Sec. | | S T R R Register of Deeds Stamp & File Number | | | | | | |
| I,do h mentin the Land 4 and Decree | Randy Kolehouse ereby certify that ioned in lines 1 and ecurrent manual of Management or by 5 above were in the of a Court of Las expressed beloweres. | , in a field under requirement 2 above were in consurvey instructions a decree of a Country established, w: | d survey on | uary 9 1 n P.A. of 1970, the tions and rules therefor Department of the inter e corner points mention an Board of Land Surv mented, re-monumente | corner points re as required for, Bureau of ned in lines 3, reyors or by a led, recovered, | A B C D E F 2 6 5 4 3 4 7 8 9 10 30 29 2 | 3 | X L 2 1 | |
| A. | | | nt and accessories an | ıd/or subsequent res | toration: | 31 32 3 | 3 34 | 35 36- | |
| K-13 | 1837 G 1939-62 W 1978 L 1981 L 1991 L | i.L.O. Notes /itness Map .C.R.C. #1134 .C.R.C. #1781 .C.R.C. #5897 | N. Brookfield K.C. Surveyor | Kooten & Assoc. | Set Post Concrete Monum 3/4" Iron Fnd. 3/4" Iron in | | KENT CO | | |
| | | | | | | ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ | | | |

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 1/16/81 and was recorded per L.C.R.C. #1781.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- K-13 Found a Standard Kent County Monument on the C/L of 4 Mile Road (gravel) running East and West, 1.0' West of the C/L of Ashley Road (gravel) running South, and 7.0' West of the C/L of Ashley Road (gravel) running North per L.C.R.C.'s #1781 and #5897 as set by Williams & Works in place of a 3/4" iron they found in a concrete monument which checked L.C.R.C. #1134 and the K.C. Surveyor's records.

L.C.R.C. #1781

L.C.R.C. #5897

K.C. Remon. Tag & Nail in NE Side P. Pole S 55°E 95.25'

K.C. Remon. Tag & Nail in W. Side 32" Maple S 25°E 131.20'

K.C. Remon. Tag & Nail in S. Side 12" Maple N 75°E 154.86'

K.C. Remon. Tag & Nail in NW Side P. Pole S 65°W 173.88'

Top C/L of MBT Box S 45°W 47.89'

KC Remon tag & nail NE side P. Pole S55°E 95.25' (m. 95.23')

KC Remon tag & nail W. side 36" Maple S25°E 131.18' (m. 131.12')

KC Remon tag & nail S. side 14" Maple N75°E 154.81' (m. 154.80')

KC Remon tag & nail NW side P. Pole S65°W 173.90' (m. 173.94')

Top C/L of MBT Box S45°W 47.89' (m. 47.70')

Kent County Monument @ NE cor. Sec. 2, T7N, R9W N90°E 24.40' (m. 24.46')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Standard Kent County Monument

Nail & K.C. remon. tag on NE side P. pole S 55° E 95.23'

Nail & K.C. remon. tag on W side 36" Maple S 25° E 131.12'

Nail & K.C. remon. tag on S side 14" Maple N 75° E 154.80'

Nail & K.C. remon. tag on NW side P. pole S 65° W 173.94'

Top C/L_MBT box S 45° W 47.70'

On C/L of gravel road running E-W

C/L of gravel road running S, East 1.0

C/L of gravel road running N, East 7.0F M

K.C. Mon., K-1, T7N, R9W, N.

RANDY 1. **LOLE**HOUSE

25854

Signed by.

Surveyor's Michigan License No.

25854

LAND SEN