

MAR 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

KENT COUNTY REMONUMENTATION

For corners in

Kent (County)

Located in: Grattan Township

Corner Code #

- 1. Public Land Survey T 8N R 9W L-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on October 28 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-2 This corner was not originally set by the G.L.O.
1961 Witness Map K.C. Surveyor 1/2" Iron

P.A. 345 1990 KENT COUNTY PEER APPROVED 10/22/98 CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-2 The 1/2" iron and all witnesses shown on the K.C. Witness Map no longer remain. Found a rebar in the C/L of Heffron Road. The found rebar is 5.4' East and 0.1' South of the intersection of 1/4 lines. No record of who set this point. Set monument at the intersection of 1/4 lines. Monument is on the C/L of Heffron Road (bit.) running East and West. Occupation line visible starting approximately 1/4 mile North and running North.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-2 Set a Standard Kent County Monument
Nail & K.C. remon. tag on W side wood fence post N 13° E 33.63'
Nail & K.C. remon. tag on NW side P. pole S 46° W 39.34'
Nail & K.C. remon. tag on NE side 10" Apple S 20° E 43.97'
Nail & K.C. remon. tag on NE side 10" Apple S 48° E 69.84'
On C/L bit. road running E-W

Signed by [Signature] Date 12/14/98
EARTH TECH
Surveyor's Michigan License No. 25854

STATE OF MICHIGAN COUNTY OF KENT RECEIVED FOR RECORD 98 DEC 23 AM 8:59 REG. OF DEEDS 11074 Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column L and row 2.

