

\$7.00
\$2.00
MAR 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 DEC 14 AM 8:00
REG. OF DEEDS
Lucy Stand

For corners in

Kent (County)	Located in:	Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>9W</u>	<u>L-9</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

11003

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on February 26 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9	1837	G.L.O. Notes	Cathcart	Set Post
	1983	L.C.R.C. #3649	John Bueche	Set K.C. Monument
	1986	L.C.R.C. #4432	R. Kolehouse	Set River Over K.C. Monument
	1991	L.C.R.C. #5901	William Byl	K.C. Monument

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 11/21/83 and was recorded per L.C.R.C. #3649.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found a Standard Kent County Monument (broken) on the C/L of 6 Mile Road (bit.) running East and West per L.C.R.C.'s #3649, #4432 and #5901 as set by John Bueche 1/2 way and on line between the Southwest and Southeast corners of Section 24. Reset broken monument.

L.C.R.C. #3649

L.C.R.C. #5901

K.C. Remon. tag & nail in W. side 6" Oak S 0° W 23.20'
K.C. Remon. tag & nail in S.W. side 12" Poplar S 55° E 48.76'
K.C. Remon. tag & nail in S.W. side 14" Poplar S 70° E 82.65'
PK nail in S. side Power pole N 80° E 122.31'
C/L 18" Poplar n 60° W 95.4'

Nail & KC Remon. tag W. side 6" Oak S00°W 23.18' (m. 23.07')
Nail & KC Remon. tag SW side 14" Poplar S55°E 48.72' (m. 48.63')
Nail & KC Remon. tag SW side 16" Poplar S70°E 82.62' (m. 82.52')
PK Nail & KC Remon. tag S. side P. Pole N80°E 122.31' (m. 122.52')
Nail & KC Remon. tag S. side 24" Poplar N60°W 95.21' (m. 95.24')
Cut "X" top W. end 12" conc. culv. N50°E 33.81' (m. 33.72')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Reset a Standard Kent County Monument

Nail & K.C. remon. tag on W side 6" Oak S 00° W 23.07'
Nail & K.C. remon. tag on SW side 14" Poplar S 55° E 48.63'
Nail & K.C. remon. tag on SW side 16" Poplar S 70°E 82.52'
Nail & K.C. remon. tag on S side P. pole N 80° E 122.52'
Nail & K.C. remon. tag on S side 24" Poplar N 60° W 95.24'
"X" cut top W end 12" conc. culv. N 50° E 33.72'
On C/L of bit. road running E-W



Signed by Randy J. Kolehouse Date 9-30-98

EARTH TECH

Surveyor's Michigan License No. 25854