

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent (County)	Located in:	Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>9W</u>	<u>L-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 DEC 14 AM 8:00
REG. OF DEEDS
Lucy Stand

11004
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 7 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13	1837	G.L.O. Notes	N. Brookfield	Set Post
	1978	L.C.R.C. #1133	Medema, Van Kooten & Assoc.	1/2" Iron
	1981	L.C.R.C. #1782	Williams & Works	Fnd. 1/2" Re-rod Over 1/2" Iron / Set K.C. Monument
	1990	L.C.R.C. #5903	William Byl	K.C. Monument P.A. 345 1990 KENT COUNTY

Note: This corner is not common with L-1, T7N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 1/9/81 and was recorded per L.C.R.C. #1782.

PEER APPROVED 9/24/98
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found a Standard Kent County Monument 5' West of the C/L of Fallsburg Park Road (gravel) running South and 7' South of the C/L of 4 Mile Road (gravel) running East and West per L.C.R.C.'s #1782 and #5903 as set by Williams & Works in place of a 1/2" re-rod they found over a 1/2" iron 1' ± below grade which checked L.C.R.C. #1133.

L.C.R.C. #1782

L.C.R.C. #5903

Nail and K.C. Remon. Tag in North West Side P. Pole S 40°W 98.39'	Nail & KC Remon. tag NW side P. Pole S40°W 98.28' (m. 98.32')
Nail and K.C. Remon. Tag in South Side 26' P. Pole S 70°W 87.47'	Nail & KC remon. tag S. side 30" Oak S70°W 87.43' (m. 87.41')
Nail and K.C. Remon. Tag in East Side T. Pole S 20°E 95.14'	Nail & KC Remon. tag E. side T. Pole S20°E 95.03' (m. 95.10')
Nail and K.C. Remon. Tag in North Side 38" Oak N 70°W 80.39'	Nail & KC Remon. tag N. side 42" Oak N70°W 80.34' (m. 80.29')
	Kent County Monument East 12.52'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13 Standard Kent County Monument
- Nail & K.C. remon. tag on NW side P. pole S 40° W 98.32'
- Nail & K.C. remon. tag on S side 30" Oak S 70° W 87.41'
- Nail & K.C. remon. tag on E side T. pole S 20° E 95.10'
- Nail & K.C. remon. tag on N side 42" Oak N 70° W 80.29'
- C/L of gravel road running S, East 5'
- C/L of gravel road running E-W, North 7'
- K.C. Mon., L-1, T7N, R9W, East 12.52'

Signed by Randy J. Kolehouse Date 9-30-98

Surveyor's Michigan License No. 25854