

\$7.00 SURVEY & REMONUMENTATION
 \$2.00
 MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

For corners in SECTION

Kent (County)	Located in:	Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>9W</u>	<u>M-3</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 DEC 14 AM 8:00
 REG. OF DEEDS
Luci Stand

11007

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 29 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3	1837	G.L.O. Notes	N. Brookfield	12" Oak
	1965	Notes	Williams & Works	Set RR Spike
	1985	L.C.R.C. #4189	R. Kolehouse	Set K.C. Monument
	1990	L.C.R.C. #5905	William Byl	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 9/24/98
 CHAIRMAN *[Signature]*

Note: This corner is common with A-3, T8N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented Randy Kolehouse on 3/9/85 and was recorded per L.C.R.C. #4189.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found a Standard Kent County Monument (4" below grade) 2' West of the C/L intersection of Montcalm Avenue (gravel) running North and South and Ellis Road (gravel) running East per L.C.R.C.'s #4189 and #5905 as set by Randy Kolehouse using witness from the 1965 notes of Williams & Works.

L.C.R.C. #4189

L.C.R.C. #5905

Nail & K.C. Remon. tag in E. side 12" Oak S 20° W 48.57'
 Nail & K.C. Remon. tag in S. side 30" Maple S 85° W 36.35'
 Nail & K.C. Remon. tag in SW side 14" Oak N 45° W 41.61'
 Nail & K.C. Remon. tag in E. side 1" dia. Wood fe. Post S 45° E 64.0'

Nail & KC Remon. tag E. side 14" Oak S20°W 48.54' (m. 48.51')
 Nail & KC Remon. tag S. side 30" Maple S85°W 36.33'
 Nail & KC Remon. tag SW side 16" Oak N32°W 41.58' (m. 41.53')
 Nail & KC Remon. tag NE side 1" dia. wood fence post S50°E 64.23'
 Nail & KC Remon. tag SE side 5" Poplar N45°E 66.07' (m. 66.05')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Standard Kent County Monument
 Nail & K.C. remon. tag on E side 14" Oak S 20° W 48.51'
 Nail & K.C. remon. tag on S side 30" Maple S 85° W 36.33'
 Nail & K.C. remon. tag on SW side 18" Oak N 35° W 41.53'
 Nail & K.C. remon. tag on NE side 1" dia. post S 50° E 64.23'
 Nail & K.C. remon. tag on SE side 6" Poplar N 45° E 66.05'
 On C/L "X" of gravel roads running N-S-E



Signed by Randy J. Kolehouse Date 9-30-98
 EARTHTECH

Surveyor's Michigan License No. 25854