

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 DEC 14 AM 8:00
REG. OF DEEDS
Lucy St. Paul

For corners in

SECTION

Kent (County)	Located in:	Grattan Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>9W</u>	<u>M-4</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

11008

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on January 29 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4	1837	G.L.O. Notes	N. Brookfield	Set Post
	1985	L.C.R.C. #4190	R. Kolehouse	Set K.C. Monument
	1991	L.C.R.C. #5906	William Byl	K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/29/98
CHAIRMAN Randy Kolehouse

Note: This corner is common with A-4, T8N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse on 3/16/85 and was recorded per L.C.R.C. #4190.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Found a Standard Kent County Monument 3' East of the C/L intersection of Montcalm Avenue (gravel) running North and South and Strotheide Road (gravel) running West per L.C.R.C.'s #4190 and #5906 as set by Randy Kolehouse using the split of R/W fences running North and South and occupation line running East and West.

L.C.R.C. #4190

L.C.R.C. #5906

Nail & K.C. Remon. tag in S. side 14" Hickory S 80° E 26.70'
Nail & K.C. Remon. tag in S. side 12" Hickory N 80° W 85.33'

Nail & KC Remon. tag S. side 14" Hickory S80°E 26.67'
Nail & KKC Remon. tag S. side 12" Hickory N80°W 85.21' (m. 85.13')
Nail & KC Remon. tag W. side 30" Maple N25°E 65.76' (m. 65.68')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Standard Kent County Monument

Nail & K.C. remon. tag on S side 14" Hickory S 80° E 26.67'
Nail & K.C. remon. tag on S side 12" Hickory N 80° W 85.13'
Nail & K.C. remon. tag on W side 32" Maple N 25° E 65.68'
Nail & K.C. remon. tag on W side 24" Oak S 20° E 103.71'
Nail & K.C. remon. tag on W side 12" Hickory N 30° W 56.14'
C/L "X" of gravel roads running N-S-W, West 3'



Signed by Randy J. Kolehouse Date 9-30-98

EARTH TECH

Surveyor's Michigan License No. 25854