

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

REG. OF DEEDS
Lucy Hand

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 DEC 14 AM 8:00

For corners in Kent (County) SECTION _____ Located in: Grattan Township Corner Code # _____

1. Public Land Survey T 8N R 9W M-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

11011

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on January 26 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9	1837	G.L.O. Notes	N. Brookfield	Set Post
	1965	Witness Map	K.C. Surveyor	Iron in Mon. Box
	1983	L.C.R.C. #3650	John Bueche	Fnd. 3/4" Iron in Mon. Box / Set K.C. Mon. in a Mon. Box
	1983	L.C.R.C. #5911	William Byl	K.C. Monument in a Monument Box

Note: This corner is common with A-9, T8N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 11/16/83 and was recorded per L.C.R.C. #3650.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found a Standard Kent County Monument in a monument box 2' South of the C/L of 6 Mile Road (bit.) running East and West and 4' West of the C/L of Montcalm Avenue (gravel) running North and South per L.C.R.C.'s #3650 and #5911 as set by John Bueche in place of a 3/4" iron he found in a monument box which checked the K.C. Surveyor's records.

L.C.R.C. #3650

L.C.R.C. #5911

K.C. Remon. tag & nail in E. side 24" Oak S 15° W 111.33'	KC Remon. tag & nail E. side 27" Oak S15°W 111.13' (m. 111.30')
PK in NW side Power Pole S 50° W 103.81'	PK nail NW side Power Pole S50°W 103.81' (m. 103.84')
"X" cut in conc. curb return S 75° W 48.03'	"X" cut in conc. curb return S75°W 48.01' (m. 47.98')


The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Standard Kent County Monument in a Monument Box

Nail & K.C. remon. tag on E side 28" Oak S 15° W 111.30'
 Nail & K.C. remon. tag on NW side P. pole S 50° W 103.84'
 "X" cut in conc. curb S 75° W 47.98'
 "X" cut in top CMP N 25° E 57.95'
 "X" cut in top CMP N 16° W 60.44'
 C/L of bit. road running E-W, North 2'
 C/L of gravel road running N-S, East 4'

P.A. 345 1990 KENT COUNTY
 PEER APPROVED *9/24/98*
 CHAIRMAN *David Huber*



Signed by Randy J. Kolehouse Date 9-30-98
 EARTH TECH

Surveyor's Michigan License No. 25854