Private Claims

LLAR 0 6 1939

SECTION

LAND CORNER RECORDATION CERTIFICATE . P.A. 1970

	4	Sept General Sept II II Name II	¥2	LIN	ng Require	inent of Act 74, Mich. P	'.A	
For corners in				KENT COUNTY REMONUMENTATION				
	Kent (County)	<u> </u>	Lo	cated in:	Grattan Township	Corner Code #		
1.	Public Land Sur	vey	ך ד	7 <u>8N</u>	R <u>9W</u>	<u>E-3N</u>		
			T		R	Witness Monument	İ	
2.	Property Contro	lling S	ר 1:	r	R R			

other code ±

19852

Register of Deeds Stamp & File Number

1.	Public Land Survey	T_8N_FI_9WE:3N
		TR
		T R Witness Monument
		T R
2.	Property Controlling	S T R
	in Section	S T R
3.	Miscellaneous	S T R
	Property in Sec.	S T R
1	Lot No	Recorded Plat

in a field survey on March 24 do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-3 1837 G.L.O. Notes L.C.R.C. #6777 1993 L.C.R.C. #8011 1995

Cathcart Thomas Starr Glaza & Associates Meander Corner Set K.C.Witness Monument K.C. Witness Monument

10 11

P.A. 345 1990 KENT COUNTY PEER APPROVED 6/25/88

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Thomás Starr on 3/15/98 and was recorded per L.C.R.C. #6777.

- В. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- E-3 Found a Standard Kent County Witness Monument on the North side of Muskrat Lake 5.1' East of a fence line running North and South and 50' ± North of the North edge of swamp per L.C.R.C.'s #6777 and #8011 as set by Thomas Starr 1880' South of E-2.

L.C.R.C. #6777

Nail & Tag in E. side 4" Oak Due North 3,44' Nail & Tag in E. side 36" Oak N 25° E 25.10' Nail & Tag in S. side 8" Thornapple S 80° E 7.48' Nail & Tag in E. side 4" Oak S 20° W 8.75'

L.C.R.C. #8011

Nail & K.C. remon tag in E side 5" Oak Due North 3.44' (m. 3.50') Nail & K.C. remon tag in E side 36" Oak N 25° E 25.10' (m. 25.20') Nail & K.C. remon tag in S side 8" Thornapple S 80° E 7.50' (m. 7.54') Nail & K.C. remon tag in E side 4" Oak S 20° W 8.76' (m. 8.77') North and South fence line West 5.1' 19.5' North to iron (All-Points capped re-rod)

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence

- Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- E-3 Standard Kent County Witness Monument

of the position of the original corner.

Nail & K.C. remon, tag on E side 5" Oak N 00° E 3.50'

Nail & K.C. remon, tag on E side 36" Oak N 25° E 25.20'

Nail & K.C. remon. tag on S side 8" Thornapple S 80° E 7.54'

Nail & K.C. remon, tag on E side 4" Oak S 20° W 8.77

All-Points capped re-rod North 19.5'

Fence line running N-S, West 5.1

RANDY I KOLEHOUSE

Surveyor's Michigan License No.

25854

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

VISED MAY 14, 1975 REVISED JAN., 1983