

**SURVEY &
REMONUMENTATION**

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>M-3</u> |
| | T <u>8N</u> R <u>10W</u> | <u>A-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:59

REG. OF DEEDS

Lucy Bond

9120

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 315 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN Harry Huber

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | | | |
|-----|------|---------------|------------|--------------------------------------|
| M-3 | 1837 | GLO | Brookfield | Set Post |
| | 1960 | Kent Co. Wit. | | 1/2" Oblong Bar |
| | 1979 | LCRC #1374 | VanKooten | 1/2" Oblong Bar next to jagged Stone |
| | 1982 | LCRC #3115 | Merdzinski | Set Kent County Monument |
| | 1988 | LCRC #4883 | Bueche | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/23/82 and was recorded per LCRC #3115

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- M-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" x 1/2" Iron next to a Slate Stone he found. Both Iron and Stone check with Kent Co. Wit. and LCRC #1374.
- LCRC #3115 & #4883
- | | | |
|--|-------|--------|
| Nail & KC Remon. tag W. side 10" Elm | N35°E | 7.63' |
| Nail & KC Remon. tag W. side 10" Elm | N30°W | 23.52' |
| Nail & KC Remon. tag N. side 6" Oak | N65°E | 17.88' |
| Nail & KC Remon. tag E. side 15" W. Cherry | S20°E | 36.89' |
| Nail & KC Remon. tag NW side 30" Maple | S25°W | 15.49' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3 Standard Kent County Monument
- | | | |
|--|-------|--------|
| New Nail & KC Remon. tag W. side 12" Elm | N35°E | 7.57' |
| New Nail & KC Remon. tag W. side 12" Elm | N30°W | 23.58' |
| New Nail & KC Remon. tag N. side 12 Oak | N65°E | 17.87' |
| Nail & KC Remon. tag E. side 20" W. Cherry | S20°E | 36.94' |
| Nail & KC Remon. tag NW side 32" Maple | S25°W | 15.51' |
- Monument is on N-S Hwy. R/W fence W. side Northland Dr.



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/6/96