

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T8N R11W	M-5 A-5
	T8N R10W	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:59

REG. OF DEEDS

Lucy St. Paul

9122

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-5	1837	GLO	Brookfield	Set Post	P.A. 345 1990 KENT COUNTY
	1963	Kent Co. Wit.		Mon. Box	PEER APPROVED <u>3/7/96</u>
	1972	LCRC #355	Spicer	3/4" Iron un Mon. Box	CHAIRMAN <u>Harry Stueber</u>
	1981	LCRC #1977	Jonker	Set Kent County Monument in Mon. Box	
	1988	LCRC #4885	Bueche	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/20/81 and was recorded per LCRC #1977.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Round Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #355.

LCRC #1977

Nail/tag 40" Maple	N30°W	77.87'
Nail/tag t. Pole	S15°E	79.73'
Nail/tag P. Pole	S74°E	77.28'
Nail/tag P. Pole	S81°W	124.80'
SE cor. hse. fnd.	N20°W	125.13'

LCRC #4885

Nail/tag 44" Maple	N30°W	77.87'
Nail/tag T. Pole	S15°E	79.73'
Nail/tag P. Pole	S75°E	83.02'
Nail/tag P. Pole	S80°W	127.20'
SE cor. hse. fnd.	N20°W	125.13'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

M-5 Standard Kent County Monument

New Nail & KC Remon. tag W. side 44" Maple	N30°W	77.87'
Nail & KC Remon. tag E. side T. Pole	S15°E	79.79'
New Nail & KC Remon. tag N. side P. Pole	S75°E	82.74'
Set Nail & KC Remon. tag S. side P. Pole	S80°W	128.18'
SE corner house foundation	N20°W	125.13'
C/L "X" bit. road E-W is N. 2'±		



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 2/6/96