

# SURVEY & REMONUMENTATION

MAR 03 1998

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners in SECTION

Kent (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

*Lucy Standa*

97 OCT 15 AM 8:43

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10080

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on June 10 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B-7	1831	G.L.O. Notes	Mullett	Set Post
	1940	Witness Map	K.C. Surveyor	Concrete Monument
	1974	L.C.R.C. #673	Medema, Van Kooten & Assoc.	Monument
	1982	L.C.R.C. #3842	C. Hay	Fnd. Monument / Set K.C. Monument
	1991	L.C.R.C. #6270	Chris Marschall	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by C. Hay on 5/18/82 and was recorded per L.C.R.C. #3842.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 Found a Standard Kent County Monument 1' South of the C/L of 7 Mile Road (bit.) running East and West on line of a tree row running South per L.C.R.C.'s #3842 and #6270 as set by C. Hay in place of a concrete monument he found 38" below grade which checked L.C.R.C. #673 and the K.C. Surveyor's records.

L.C.R.C. #3842

Nail and remon. tag in West face of wood guard post, North 18.64'  
Nail and remon. tag in East face of wood guard post, N 45°W 35.10'  
Nail and remon. tag in West face of wood guard post, N 45°E 32.25'  
Nail and remon. tag in NW face of 28" Oak S 35°W 47.27'  
Nail and remon. tag in East face of 10" Oak South 38.52'

L.C.R.C. #6270

Nail & Tag E sd. 12" Oak South 38.58'  
Nail & Tag NW sd. 34" Oak S 35 W 47.67'  
Nail & Tag W sd. Guard Post N 45 E 32.19'  
Nail & Tag E sd. Guard Post North 18.66'  
Nail & Tag E sd. Guard Post N 45 W 35.04'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 Standard Kent County Monument

Nail & K.C. remon. tag on E side 12" Oak South 38.58'  
Nail & K.C. remon. tag on NW side 34" Oak S 35° W 47.67'  
Nail & K.C. remon. tag on W side guard post N 45° E 32.19'  
Nail & K.C. remon. tag on E side guard post North 18.66'  
Nail & K.C. remon. tag on E side guard post N 45° W 35.04'

Signed by Randy J. Kolehouse Date 8/12/97

EARTH TECH

Surveyor's Michigan License No. 25854

P.A. 345 1990 KENT COUNTY

PEER APPROVED 6/26/97  
CHAIRMAN Harry Hubbell

