

**SURVEY & REMONUMENTATION**

MAR 03 1998

\$7.00  
\$2.00

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 NOV 14 AM 9:01  
REG. OF DEEDS  
*Tim Staud*

10330

Register of Deeds Stamp & File Number

For corners in

Kent (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>C-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on August 19 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-8	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Witness Map	K.C. Surveyor	2" Iron
	1974	L.C.R.C. #673	Medema, Van Kooten & Assoc.	2" Round Iron
	1981	L.C.R.C. #2360	Jonker Land Surveys	Fnd. 2" Crimped Iron / Set K.C. Monument
	1991	L.C.R.C. #6280	Chris Marschall	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 11/19/81 and was recorded per L.C.R.C. #2360.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-8 Found a Standard Kent County Monument 30' ± South of a wooden fence running East and West and 75' ± East of the Southeast corner of wooden fence (fence surrounds horse training pasture) per L.C.R.C.'s #2360 and #6280 as set by Rob Jonker in place of a 2" x 30" crimped iron he found which checked L.C.R.C. #673 and the K.C. Surveyor's records.

L.C.R.C. #2360

Remon. tag on W side 10" Maple, North 7.26'  
Remon. tag on S side 20" Oak N84°E 41.6'  
Remon. tag on S side 12" Oak N78°W 32.08'

L.C.R.C. #6280

Nail & Tag W sd. 12" Maple N 0 E 7.24'  
Nail & Tag NW sd. 36" Oak S 80 W 44.27'  
Nail & Tag S sd. 16" Oak N 80 W 32.20'  
Nail & Tag N sd. 10" Cherry N 80 E 25.77'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-8 Standard Kent County Monument

Nail & K.C. remon. tag on W side 12" Maple North 7.24'  
Nail & K.C. remon. tag on NW side 36" Oak S 80° W 44.27'  
Nail & K.C. remon. tag on S side 16" Oak N 80° W 32.20'  
Nail & K.C. remon. tag on N side 10" Cherry N 80° E 25.77'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 8/28/97

CHAIRMAN [Signature]

Date 9/23/97

Signed by Randy J. Kolehouse

EARTH TECH

Surveyor's Michigan License No. 25854

