

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE
 CORNER
 RECEIVED

03 AUG 25 1993

For corners in
 Kent

(County)

Located In:

Corner Code //

- | | | | |
|---------------------------------------|------|-------|-----|
| 1. Public Land Survey | T 8N | R 10W | D-2 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling
in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous
Property in Sec. | S | T | R |
| | S | T | R |

6818

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			●		4		3		2			
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wallace E. Glaza in a field survey on July 22 1993
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration

L.C.R.C. No. 2093 Found capped iron

Centerline S. end concrete culvert	SW 25.75'
Centerline N. end concrete culvert	NW 26.64'
Centerline blacktop	N 5.0'
Fence to South	W 6.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-2 (center of Section 5, T8N, R10W, Cannon Township, Kent County, Michigan)

Found capped iron (illegible) using above witnesses. Verified capped iron to
 be within 0.07' N & S and 0.07' E & W of intersection of 1/2 lines. Accepted
 capped iron as corner.

Replaced capped iron with standard 4" x 30" Harrison Monument.

South 1/2 corner to center	2670.28'
West 1/2 corner to center	2628.20'
North 1/2 corner to center	3440.69
East 1/2 corner to center	2629.35'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-2 (4" x 30" Harrison Monument)

1) Nail & tag in 6" Elm (6'± above ground)	S30°E	48.10'
2) Nail & tag in 12" Twin Cherry (6'± above ground)	S10°W	25.15'
3) Nail & tag in 36" Box Elder	N10°W	172.39'
4) NE corner barn	S80°W	423.14'
5) Centerline of bit. road	North	5.0'

Signed by Wallace E. Glaza
 Glaza & Associates, Inc.

Date 7-26-93

Surveyor's Michigan License No. 31592