

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 DEC 15 AM 10:43
REG. OF DEEDS
Lucy J. Bond

10395

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on August 15 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Witness Map	K.C. Surveyor	Iron & Stone
	1981	L.C.R.C. #2044	Glaza & Associates	"T" Iron
	1985	L.C.R.C. #4054	Exxel Engineering	Fnd. "T" Iron / Set K.C. Monument
	1991	L.C.R.C. #6291	Chris Marschall	K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/26/97
CHAIRMAN *[Signature]*

Note: This corner is not common with D-1, T7N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 1/3/85 and was recorded per L.C.R.C. #4054.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found a Standard Kent County Monument 200' ± North of the C/L of 4 Mile Road (gravel) running East and West and 100' ± East of the Northeast corner of House #5991 per L.C.R.C.'s #4054 and #6291 as set by Exxel Engineering 16.97' South of "T" iron per L.C.R.C. #2044.

L.C.R.C. #4054

- Nail & remon tag in S sde 8" Oak S73°E 5.94'
- Nail & remon tag in W sde 14" Oak S15°W 27.36'
- Nail & remon tag in NW sde 8" W. Cherry S45°W 34.68'
- Nail & remon tag in N sde 15" Oak S80°W 23.22'

L.C.R.C. #6291

- Nail & Tag N sd. 15" Hickory S 80 W 23.21'
- Nail & Tag E sd. 8" W. Cherry S 45 W 34.53'
- Nail & Tag W sd. 14" Oak S 15 W 27.36'
- Nail & Tag S sd. 10" Oak S 73 E 5.97'
- Nail & Tag W sd. 16" Oak N 28 E 31.45'
- Nail & Tag NE sd. 14" Hackberry N 60 W 23.46'
- At the foot of the hill to East

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13 Standard Kent County Monument
- Nail & K.C. remon. tag on N side 15" Hickory S 80° W 23.21'
 - Nail & K.C. remon. tag on E side 8" W. Cherry S 45° W 34.53'
 - Nail & K.C. remon. tag on W side 14" Oak S 15° W 27.36'
 - Nail & K.C. remon. tag on S side 10" Oak S 73° E 5.97'
 - K.C. Mon. D-1, T7N, R10W, West 284.12'

Signed by *Randy J. Kolehouse* Date 11/20/97
EARTH TECH

Surveyor's Michigan License No. 25854

