

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION**

For corners in

Kent  
(County)

Located in: Cannon  
Township

Corner Code #

- |                                    |             |              |            |
|------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey              | T <u>8N</u> | R <u>10W</u> | <u>G-1</u> |
|                                    | T _____     | R _____      | _____      |
|                                    | T _____     | R _____      | _____      |
|                                    | T _____     | R _____      | _____      |
| 2. Property Controlling in Section | S _____     | T _____      | R _____    |
|                                    | S _____     | T _____      | R _____    |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____      | R _____    |
|                                    | S _____     | T _____      | R _____    |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 OCT 15 AM 8:45  
REG. OF DEEDS  
*Eric S. Bond*

**10115**

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 24 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-1	1831	G.L.O. Notes	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	N/A	Witness Map	K.C. Surveyor	N/A	PEER APPROVED <u>6/26/97</u>
	1954-72	Notes	Williams & Works	Iron	CHAIRMAN <u>Ferry Duke</u>
	1974	L.C.R.C. #688	Exxel Engineering	1/2" Iron	
	1984	L.C.R.C. #4043	William Byl	Fnd. 1/2" Iron / Set K.C. Monument	
	1988	L.C.R.C. #4844	J. Bueche	K.C. Monument	

Note: This corner is not common with G-13, T9N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 12/4/84 and was recorded per L.C.R.C. #4043.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-1 Found a Standard Kent County Monument on the Township line 48' ± North of the C/L of 10 Mile Road (bit.) running East and West and 10' ± East of the C/L of Bush Road (gravel) running South per L.C.R.C.'s #4043 and #4844 as set by William Byl 1.06' North of a 1/2" iron he found 112.09' East of the Southwest corner of Section 34, T9N, R10W, and 1.06' South of the South line of Section 34 which checked L.C.R.C. #688, the 1954-72 notes of Williams & Works, and the K.C. Surveyor's records.

L.C.R.C. #4043

L.C.R.C. #4844

Nail & tag, S sd. MBT pole S 60 W 98.14'  
Boat spike, in C/L 10 Mile Rd. S 00 W 47.64'

PK Nail in S sde P pole S 63 W 46.64'  
Remon nail & tag W sde MBT pole S 36 W 98.14'  
Boat spike in C/L 10 Mile Rd S 00 W 47.64'  
C/L 10 Mile Rd is S 44' M/L  
K.C. Mon G-13 is W 112.09'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-1 Standard Kent County Monument

- Nail & K.C. remon. tag on S side P. pole S 63° W 46.64'
- Nail & K.C. remon. tag on W side MBT pole S 36° W 98.14'
- Boat spike in C/L 10 Mile Rd. S 00° W 47.64'
- K.C. Mon. G-13, T9N, R10W, West 112.09'

Signed by Randy J. Kolehouse Date 8/12/97  
EARTH TECH

Surveyor's Michigan License No. 25854

