

SURVEY & REMONUMENTATION

\$7.00
\$2.00 MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in **SECTION**

<u>Kent</u> (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 NOV 14 AM 9:02
REG. OF DEEDS
Lucy Standa

10334
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on August 19 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6	1831	G.L.O. Notes	Mullett	Set Post
	1979	L.C.R.C. #1268	Exxel Engineering	"T" Iron
	1981	L.C.R.C. #2427	Jonker Land Surveys	Fnd. "T" Iron / Set K.C. Monument
	1991	L.C.R.C. #6312	Chris Marschall	K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/28/97
CHAIRMAN Harry Huber

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 12/5/81 and was recorded per L.C.R.C. #2427.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found a Standard Kent County Monument at the intersection of a fence line running North and South and a tree row running West per L.C.R.C.'s #2427 and #6312 as set by Rob Jonker in place of a "T" iron he found in a pile of stones which checked L.C.R.C. #1268.

L.C.R.C. #2427

L.C.R.C. #6312

Remon. tag on N side 20" W. Cherry S69°W 7.76'
Remon. tag on NW side 8" W. Cherry S17°W 21.46'
Remon. tag on N side 5" W. Cherry N85°E 24.03'
Remon. tag on NW side 5" W. Cherry N48°E 14.47'

Nail & Tag N sd. Twin 24" W. Cherry S 69 W 7.70'
Nail & Tag NW sd. 10" W. Cherry S 17 W 21.40'
Nail & Tag NW sd. 8" W. Cherry N 48 E 14.67'
Nail & Tag N sd. 10" W. Cherry N 85 E 24.17'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 Standard Kent County Monument
Nail & K.C. remon. tag on N side Twin 24" Cherry S 69° W 7.70'
Nail & K.C. remon. tag on NW side 10" W. Cherry S 17° W 21.40'
Nail & K.C. remon. tag on NW side 8" W. Cherry N 48° E 14.67'
Nail & K.C. remon. tag on N side 10" W. Cherry N 85° E 24.17'

Signed by Randy J Kolehouse Date 9/23/97

EARTH TECH

Surveyor's Michigan License No. 25854

