

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00  
MAR 03 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 DEC 15 AM 10:44  
REG. OF DEEDS  
*W. J. Bond*

For corners in

Kent (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>H-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10403

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kohhouse, in a field survey on June 13 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-8	Description	Witness Map	K.C. Surveyor	Monument
	This corner was not originally set by the G.L.O.			
	1935	Witness Map	K.C. Surveyor	Monument
	1935-66	Survey Records	Williams & Works	Concrete Monument
	1968-86	Survey Records	Williams & Works	"T" Iron
	1975	L.C.R.C. #876	Medema, Van Kooten & Assoc.	"T" Iron

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/4/97  
CHAIRMAN Harry Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-8 Found a "T" iron 4' West of the C/L of Sunfish Lake Avenue (bit.) running North and South and the C/L of Kreuter Road (bit.) running West per L.C.R.C. #876 and the K.C. Surveyor's records. "T" Iron is 15.8' North and 3.0' East of the intersection of 1/4 lines. Accepted "T" iron as Center of Section.

L.C.R.C. #876

- Centerline Blacktop road E 3.50'
- Nail in SW side 34" and 14" Double Maple NW 58.36' (m. 58.78')
- Nail in SW side 30" Maple NE 53.84'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-8 Replaced "T" Iron with a Standard Kent County Monument
- Nail & K.C. remon. tag on SW side Twin 10" Maple S 80° E 42.90'
  - Nail & K.C. remon. tag on SE side 32" Maple N 60° E 53.62'
  - Nail & K.C. remon. tag on NE side 14"-36" Maple N 45° W 59.56'
  - Nail & K.C. remon. tag on N side 36" Maple S 80° W 119.02'
  - Nail & K.C. remon. tag on SW side 34" & 14" Double Maple N 45° W 58.78'

Signed by Randy J Kohhouse Date 12/5/97

EARTH TECH

Surveyor's Michigan License No. 25854