

SURVEY & REMONUMENTATION

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 OCT 15 AM 8:47
 REG. OF DEEDS
Lucy Bond

10146

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on June 25 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8	1831	G.L.O. Notes	Mullett	Set Post
	1941	Witness Map	K.C. Surveyor	Monument
	1972	L.C.R.C. #230	Williams & Works	Concrete Monument
	1981	L.C.R.C. #2446	Jonker Land Surveys	Fnd. Concrete Monument / Set K.C. Monument
	1984	L.C.R.C. #3995	Williams & Works	Reset K.C. Monument
	1989	L.C.R.C. #5275	J. Bueche	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 12/9/81 and was recorded per L.C.R.C. #2446.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found a Standard Kent County Monument 3' South of the C/L intersection of Kreuter Road (bit.) running East and West and Giles Road (bit.) running South per L.C.R.C.'s #2446, #3995 and #5275 as set by Rob Jonker in place of a 4" x 48" concrete monument he found which checked L.C.R.C. #230 and the K.C. Surveyor's records.

L.C.R.C. #2446

- Remon. tag on E. side p. pole N 03° W 56.65'
- Remon. tag on SE side 9" Walnut N 31° E 40.07'
- Remon. tag on NE side 10" Ash N 27° W 41.20'
- Remon. tag on N. side 6" Elm S 67° W 81.26'

L.C.R.C. #5275

- Remon. tag & nail NW side 20" Oak S 40° W 70.15'
- Remon. tag & nail on E side p. pole N 03° W 56.40'
- Remon. tag & nail on SE side 12" Walnut N 31° E 40.04'
- Remon. tag & nail on NE side 12" Ash N 27° W 41.00'
- Remon. tag & nail on N side 10" Elm S 67° W 81.27'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-8 Standard Kent County Monument
- Nail & K.C. remon. tag on NW side 20" Oak S 40° W 70.15'
 - Nail & K.C. remon. tag on E side P. pole N 03° W 56.40'
 - Nail & K.C. remon. tag on SE side 12" Walnut N 31° E 40.04'
 - Nail & K.C. remon. tag on NE side 12" Ash N 27° W 41.00'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/24/97

CHAIRMAN *Ham Shubert*



Signed by *Randy J. Kolehouse* Date 8/12/97

EARTH TECH

Surveyor's Michigan License No. 25854