

SURVEY & REMONUMENTATION

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>10W</u>	<u>K-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 OCT 15 AM 8:48
REG. OF DEEDS
David Stand

10151

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on June 26 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13	1831	G.L.O. Notes	Mullett	Set Post
	1968	Witness Map	K.C. Surveyor	Stone (Iron)
	1981	L.C.R.C. #3308	Glaza & Associates	"T" iron
	1983	L.C.R.C. #3484	J. Bueche	Fnd. "T" Iron / Set K.C. Monument
	1989	L.C.R.C. #5280	J. Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/24/97
CHAIRMAN Henry Kuberski

Note: This corner is not common with K-1, T7N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by J. Bueche on 7/25/83 and was recorded per L.C.R.C. #3484.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found a Standard Kent County Monument 2.0' ± East of the C/L of Giles Road (gravel) running North and 2.5' ± North of the C/L of 4 Mile Road (gravel) running East and West per L.C.R.C.'s #3484 and #5280 as set by J. Bueche in place of a "T" iron he found which checked L.C.R.C. #3308 and the K.C. Surveyor's records.

L.C.R.C. #3484

L.C.R.C. #5280

K.C. remon. tag & nail in N side 8" Elm S 65° W 49.46'	Remon tag & nail in N side 10" Elm S 65° W 49.55'
K.C. remon. tag & nail in W side 16" Maple N 10° E 122.62'	Remon tag & nail in W side 18" Maple N 10° E 122.62'
K.C. remon. tag & nail in S side group - 6" Elms N 70° E 92.00'	Remon tag & nail in S side group - 8" Elms N 70° E 92.00'
K.C. remon. tag & nail in N side 18" W. Cherry S 75° E 108.71'	Remon tag & nail in N side 20" W. Cherry S 75° E 108.71'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Standard Kent County Monument

- Nail & K.C. remon. tag on N side 10" Elm S 65° W 49.55'
- Nail & K.C. remon. tag on W side 18" Maple N 10° E 122.62'
- Nail & K.C. remon. tag on S side group - 8" Elms N 70° E 92.00'
- Nail & K.C. remon. tag on N side 20" W. Cherry S 75° E 108.71'



Signed by Randy J. Kolehouse Date 8/12/97

Surveyor's Michigan License No. 25854