

SURVEY & REMONUMENTATION

MAR 03 1998

\$7.00
\$2.00

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 DEC 15 AM 10:44
REG. OF DEEDS

For corners in SECTION

Kent (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>L-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10414

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on October 11 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-2 This corner was not originally set by the G.L.O.

N/A	Witness Map	K.C. Surveyor	Iron
1979	L.C.R.C. 1295	Exxel Engineering	1" Iron Pipe

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/20/97

CHAIRMAN Randy Kolehouse

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-2 Found a 1" iron pipe 1' East of a fence line running South, 1' North of a fence line running East and 35' ± North of the C/L of a two-track dirt road running East and West per L.C.R.C. 1295. Iron pipe is 2.5' North and 2.8' East of the intersection of 1/4 lines. Accepted iron pipe as Center of Section.

L.C.R.C. #1295

- Nail in sde 38" Oak South 43.80'
- Nail in sde 15" Oak ESE 5.53'
- Nail in sde 22" Oak ENE 33.92'
- Nail in sde 10" W. Cherry SW 36.85'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-2 Replaced 1" Iron Pipe with a Standard Kent County Monument

- Nail & K.C. remon. tag on NE side 38" Oak S 26° West 43.80'
- Nail & K.C. remon. tag on S side 16" Oak S 50° East 5.90'
- Nail & K.C. remon. tag on S side 24" Oak N 81° E 35.12'
- Nail & K.C. remon. tag on NW side 12" Cherry S 69° W 36.85'

Signed by Randy J. Kolehouse
EARTH TECH

Date 11/24/97

Surveyor's Michigan License No. 25854

