

SURVEY & REMONUMENTATION

\$7.00
\$2.00
MAR 03 1998
SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>L-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REG. OF DEEDS
Lucy Bond
97 DEC 15 AM 10:45
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10416
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on November 24 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-4 This corner was not originally set by the G.L.O.

No information on record. Also checked Kent County Surveyor's witness map and found no information pertaining to this corner.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/20/97
CHAIRMAN Randy Kolehouse

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-4 Found a "T" iron on line of a fence line running East and West. No information on record for this iron. "T" iron is 3.3' South and 2.0' West of the intersection of 1/4 lines. Accepted "T" iron as Center of Section.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-4 Replaced "T" Iron with a Standard Kent County Monument
- Nail & K.C. remon. tag on E side 8" Oak S 20° E 18.80'
- Nail & K.C. remon. tag on N side 32" Oak West 1.82'
- Nail & K.C. remon. tag on E side 10" Cherry North 15.21'
- Nail & K.C. remon. tag on N side 30" Oak N 90° E 33.60'



Signed by Randy J. Kolehouse
EARTH TECH

Date 11/28/97

Surveyor's Michigan License No. 25854

