

SURVEY & REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

For corners in **SECTION**

<u>Kent</u> (County)	Located in: Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10W</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 OCT 15 AM 8:48
 REG. OF DEEDS
Lucy Strand
10154
 Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 1 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9	1831	G.L.O. Notes	Mullett	Set Post
	1934	Witness Map	K.C. Surveyor	Iron on Stone
	1978	L.C.R.C. #1152	Williams & Works	1" Iron Pipe
	1981	L.C.R.C. #2450	Jonker Land Survey	Fnd. 1" Iron / Set K.C. Monument
	1989	L.C.R.C. #5284	J. Bueche	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 12/8/81 and was recorded per L.C.R.C. #2450.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found a Standard Kent County Monument on the C/L of 6 Mile Road (bit.) running East and West on line of a tree/fence line running South and a tree row running North per L.C.R.C.'s #2450 and #5284 as set by Rob Jonker in place of a 1" iron he found at grade in a pile of stones 12" below grade which checked L.C.R.C. #1152 and the K.C. Surveyor's records.

L.C.R.C. #2450

Remon. tag on W side 26" Maple N 13° E 39.40'
 Remon. tag on W side 34" Maple S 02° W 27.30'
 Remon. tag on NW side 5" Maple S 53° W 49.13'
 Remon. tag on S side 42" Oak N 62° W 58.40'

L.C.R.C. #5284

Remon. tag & nail on W side 30" Maple N 13° E 39.36'
 Remon. tag & nail on W side 36" Maple S 02° W 27.26'
 Remon. tag & nail on NW side 7" Maple S 53° W 49.13'
 Remon. tag & nail on S side 48" Oak N 62° W 59.63'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


L-9 Standard Kent County Monument

Nail & K.C. remon. tag on W side 30" Maple N 13° E 39.36'
 Nail & K.C. remon. tag on W side 36" Maple S 02° W 27.26'
 Nail & K.C. remon. tag on NW side 7" Maple S 53° W 49.13'
 Nail & K.C. remon. tag on S side 48" Oak N 62° W 59.63'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/24/97

CHAIRMAN *Harry H. Hube*



Signed by *Randy J. Kolehouse* Date 9/12/97
 EARTH TECH

Surveyor's Michigan License No. 25854

