

SURVEY & REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in **SECTION**

Kent (County)	Located in:	Cannon Township	Corner Code #
1. Public Land Survey	T <u>8N</u>	R <u>10W</u>	<u>L-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 OCT 15 AM 8:48
 REG. OF DEEDS
Lucy Bond
10156

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 1 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13	1831	G.L.O. Notes	Mullett	Set Post
	1969	Notes	Williams & Works	N/A
	1981	L.C.R.C. #3308	Glaza & Associates	RR Spike
	1985	L.C.R.C. #4055	Exxel Engineering	Fnd. RR Spike / Set K.C. Monument
	1989	L.C.R.C. #5286	J. Bueche	K.C. Monument

Note: This corner is not common with L-1, T7N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 10/31/89 and was recorded per L.C.R.C. #4055.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found a Standard Kent County Monument 10' East and 2' South of the C/L intersection of Mc Cabe Avenue (bit.) running North and South and 4 Mile Road (gravel) running East and West per L.C.R.C.'s #4055 and #5286 as set by Exxel Engineering in place of a RR spike they found which checked L.C.R.C. #3308 and the K.C. Surveyor's records.

L.C.R.C. #4055

L.C.R.C. #5286

Nail & remon tag in N sde 12" Hickory S 75° W 71.04'
 Nail & remon tag in E sde 10" Walnut S 04° E 78.43'
 Nail & remon tag in N sde 7" Hickory S 74° E 75.75'


Nail & remon. tag in N side 14" Hickory S 75° W 71.04'
 Nail & remon. tag in E side 12" Walnut S 04° E 78.43'
 Nail & remon. tag in N side 10" Hickory S 74° E 75.75'
 SE cor. house fndn. N 38° E 148.44'
 PK in remon. tag in N side t. pole N 53° W 73.01'
 "T" iron East 12.58'
 K.C. Mon. (L-1, 7-10) West 64.23'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Standard Kent County Monument

Nail & K.C. remon. tag on N side 14" Hickory S 75° W 71.04'
 Nail & K.C. remon. tag on E side 12" Walnut S 04° E 78.43'
 Nail & K.C. remon. tag on N side 10" Hickory S 74° E 75.75'
 SE cor. hse. fnd. N 38° E 148.44'
 K.C. Mon. L-1, T7N, R10W, West 64.23'



Signed by Randy J. Kolehouse Date 8/12/97

Surveyor's Michigan License No. 25854

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/24/97
 CHAIRMAN Harold Huber