

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent (County)

Located in: Cannon Township

Corner Code #

- 1. Public Land Survey T 8N R 10W M-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

REG. OF DEEDS

Handwritten signature

97 OCT 15 AM 8:49

STATE OF MICHIGAN COUNTY OF KENT RECEIVED FOR RECORD

10164

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 1 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-9 1831 G.L.O. Notes Mullett Set Post
1941 Witness Map K.C. Surveyor Iron
1978 L.C.R.C. #1151 Williams & Works "T" Iron
1980 L.C.R.C. #1403 Williams & Works "T" Iron (A-9, T8N, R9W)
1981 L.C.R.C. #1904 Jonker Land Survey Fnd. "T" Iron / Set K.C. Monument
1989 L.C.R.C. #5294 J. Bueche K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/24/97 CHAIRMAN Randy Kolehouse

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column M and row 9.

Note: This corner is common with A-9, T8N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 7/17/81 and was recorded per L.C.R.C. #1904.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-9 Found a Standard Kent County Monument at the C/L intersection of Tiffany Avenue (gravel) running North and South and 6 Mile Road (gravel) running East and West per L.C.R.C.'s #1904 and #5294 as set by Rob Jonker in place of a "T" iron he found over a 2"x2"x2' solid point bar 1' below grade which checked L.C.R.C.'s #1403, #1151, and the K.C. Surveyor's records.

L.C.R.C. #1904

L.C.R.C. #5294

- Remon. tag on NW side 18" Ash N 56° E 50.13'
Remon. tag on NE side 21" Ash N 20° E 82.96'
Remon. tag on NE side Triple 9" Hickory N 62° W 64.16'
Remon. tag on SE side guy pole S 58° W 53.15'

- Remon. tag & nail on SE side 12" Ash N 60° E 54.87'
Remon. tag & nail on NE side 24" Ash N 20° E 82.88'
Remon. tag & nail on NE side Triple 12" Hickory N 62° W 64.19'
Remon. tag & nail on SE side guy pole S 58° W 53.15'
Remon. tag & nail on SE side P.P. N 55° E 82.75'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 Standard Kent County Monument

- Nail & K.C. remon. tag on SE side 12" Ash N 60° E 54.87'
Nail & K.C. remon. tag on NE side 12" Ash N 20° E 82.88'
Nail & K.C. remon. tag on NE side Triple 12" Hickory N 62° W 64.19'
Nail & K.C. remon. tag on SE side Guy pole S 58° W 53.15'

Signed by Randy J. Kolehouse Date 8/12/97

EARTH TECH

Surveyor's Michigan License No. 25854

