

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC 27 AM 9:05

W. R. Byl
REG. OF DEEDS

7912

Register of Deeds Stamp & File Number

For corners in
KENT COUNTY

(County)

Located In: Corner Code #

- | | | | | | |
|---------------------------------------|---|----|---|------|------|
| 1. Public Land Survey | T | 8N | R | 12W | M-12 |
| | T | | R | also | |
| | T | 8N | R | 11W | A-12 |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

I, William R. Byl, in a field survey on Oct. 20, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|------|------|---------------|--------------|---------------------------------|
| M-12 | 1837 | GLO | Brookfield | Set Post |
| | | Kent Co. Wit. | | Sq. Conc. Mon. with brass plate |
| | 1979 | LCRC #1334 | Byl | Sq. Conc. Mon. |
| | 1984 | LCRC #3742 | Chettleburgh | 6 1/2" Sq. Conc. Mon. |
| | 1985 | LCRC #4156 | Chettleburgh | Set Kent County Monument |
| | 1990 | LCRC #5434 | Starr | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thom. M. Chettleburgh on 4/3/85 and recorded per LCRC #4156.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas M. Chettleburgh in place of the 6 1/2" square Conc. Mon. he found. Said square Conc. Mon. checks with Kent Co. Wit. and LCRC's #1334 & #3742.

LCRC #4156 & 5434

- Nail & KC Remon. tag NW side 29" Willow N41°E 152.44'
- Nail & KC Remon. tag SW side Light Pole S50°E 175.68'
- Nail & KC Remon. tag E. side 27" Maple S13°E 275.12'
- Nail & KC Remon. tag NW side 12" Beech S53°W 161.85'
- Nail & KC Remon. tag W. side 29" Maple N08°W 236.24'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/22/94
CHAIRMAN *Henry Huber*

Chain link fence East 2'; C/L bit. dr. to main. bldg. is S. 98'
In Dwight Lydell Park - Between fish ponds

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Standard Kent County Monument

- New Nail & KC Remon. tag NW side 36" Willow N41°E 151.98'
 - Nail & KC Remon. tag SW side Light Pole S50°E 175.73'
 - New Nail & KC Remon. tag E. side 30" Maple S13°E 275.17'
 - New Nail & KC Remon. tag NW side 18" Beech S53°W 161.79'
 - New Nail & KC Remon. tag W. side 33" Maple N08°W 236.33'
- Chain link fence East 2'; C/L bit. dr. to main. bldg. is South 98'
In Dwight Lydell Park - Between fish ponds



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 12/07/94