

Yw

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 28 AM 11:50

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey
 - T 7N R 12W M-1
 - T 7N R 11W A-1
 - T 8N R 12W M-12
 - T 8N R 11W A-13
- 2. Property Controlling in Section
 - S ___ T ___ R ___
 - S ___ T ___ R ___
- 3. Miscellaneous Property in Sec.
 - S ___ T ___ R ___
 - S ___ T ___ R ___

Eric J. Bond
REG. OF DEEDS

7374

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on June 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-1 1837 GLO Brookfield Set Post
- 1944 Kent Co. Wit. Concrete Monument
- 1973 LCRC #569 (A-1 7-11) Spicer Monument
- 1982 LCRC #3169 (A-1 7-11) Jonker Set Kent County Monument
- 1990 LCRC #5435 Starr Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11/10/82 and was recorded per LCRC #3169

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Concrete Monument he found. Said Concrete Monument checks with Kent Co. Wit. & LCRC #569.

LCRC #3169

LCRC #5435

Remon. tag 36" W. Cherry S15°W 2.10' same witnesses as LCRC #3169

Remon. tag 4" Elm? N00°E 11.35'

Remon. tag 8" Box Elder S80°W 7.35'

SE cor. septic tank N75°W 13.67'

C/L Bertha St., South 25' m/l

C/L W. River Dr. Easterly 100' m/l

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN *Harry H. Hulse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-1 Standard Kent County Monument
- New Nail & KC Remon. tag W. side 48" W. Cherry S15°W 2.12'
- New Nail & KC Remon. tag W. side 8" Elm N00°E 11.34'
- New Nail & KC Remon. tag S. side 12" Box Elder S80°W 7.41'
- SE cor. septic tank N75°W 13.64'
- C/L Bertha St., South 25' m/l
- C/L W. River Dr. Easterly 100' m/l



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11-17-94