

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>B-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 26 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:51

9028

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	●											
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-5	1837	GLO	Whitcomb	Set Post
	1949	Williams & Works		Iron Stake
	1984	LCRC #3749	Kolehouse	Set Kent County Monument
	1994	LCRC #6894	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/17/96
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 2/25/84 and was recorded per LCRC #3749

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehosue in place of the 1" Iron he found. Said Iron checks with Williams & Works information and Kent Co. Wit.
LCRC #3749 & #6894

Nail & KC Remon. tag W. side Twin 12" Maple	North	6.15'
Nail & KC Remon. tag S. side 12" Maple	West	31.60'
Nail & KC Remon. tag NW side 10" Maple	S45°W	21.05'
Nail & KC Remon. tag E. side 8" Maple	South	10.92'
Nail & KC Remon. tag SE side 12" Maple	N30°E	15.23'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 Standard Kent County Monument

Nail & KC Remon. tag W. side Tri. 12" Maple	N00°E	6.15'
Nail & KC Remon. tag S. side 14" Maple	S90°W	31.71'
Nail & KC Remon. tag NW side 12" Maple	S45°W	21.00'
Nail & KC Remon. tag E. side 10" Maple	S00°W	10.81'
Nail & KC Remon. tag SE side 14" Maple	N30°E	15.34'

On remains of fence N-S-W



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/6/96