

REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 11W	B-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 SEP 13 PM 12:05
REG. OF DEEDS
Lucy Spindel

9355

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breiteis, in a field survey on Aug. 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-6 1837---GLO---Not Set
- 1940---Williams & Works---Ran N-S 1/4 line for survey, No corner set
- 1977---LCRC #1232---Byl---"T" Iron
NE cor. hse. SW 103.25' Iron S 33.01' Iron W 2.75'
Trans. Pole NNE 60.8'
- 1991---Research---Roosien---Set PK Nail per LCRC #1232

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/22/96
CHAIRMAN Harry Kupiec

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-6 Found RR Spike per the following witnesses:
NE cor. hse. SW 103.25' Nail in face Trans. Pole NNE 60.75'
Iron (Byl) S 32.95'

Said RR Spike is 0.1' E. and 0.1' S. from intersection of 1/4 lines and agrees with survey measurements of others.

The RR Spike is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-6 Set Standard Kent County Monument in place of the RR Spike
- Set Nail & KC Remon. tag E. side Trans. Pole N20°E 61.12'
- Set Nail & KC Remon. tag SE side 16" Elm N65°E 66.81'
- Capped Rerod (Byl) South 32.95'
- NE corner Hse. foundation S45°W 103.25'



Signed by Kirk Breiteis
Surveyor's Michigan License No. 30077

Date 9/4/96