

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>B-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:51

REG. OF DEEDS

9029

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | | | |
|-----|------|---------------|-----------|--------------------------|
| B-7 | 1837 | GLO | Whitcomb | Set Post |
| | | Kent Co. Wit. | | Pointed Stone |
| | 1975 | LCRC #819 | Bonnema | "T" Iron |
| | 1977 | LCRC #1232 | Byl | "T" Iron |
| | 1984 | LCRC #3835 | Kolehouse | Set Kent County Monument |
| | 1994 | LCRC #6895 | Byl | Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 5/8/84 and was recorded per LCRC #3835.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- B-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the "T" Iron over a Conc. Mon. he found. Both "T" Iron and Conc. Mon. check with Kent Co. Wit. and LCRC's #819 & #1232.
- LCRC #3835 # #6895
- Nail & KC Remon. tag E. side 20" Hickory South 30.21' Nail & KC Remon. tag
Nail & KC Remon. tag W. side 18" Hickory N05°W 34.97' E. side 44" Oak S05°E 61.52'
Nail & KC Remon. tag SW side Tri. 8" Ash N55°W 61.43' Nail & KC Remon. tag
Nail & KC Remon. tag NW side 16" Maple S45°W 43.15' S. side P. Pole N75°E 98.69'
Iron in Mon. Box N40°W 5.09'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- B-7 Standard Kent County Monument
- | | | |
|--|-------|--------|
| New Nail & KC Remon. tag W. side 24" Hickory | N05°W | 34.95' |
| Nail & KC Remon. tag SW side Tri. 8" Ash | N55°W | 61.43' |
| Nail & KC Remon. tag NW side 18" Maple | S45°W | 43.10' |
| Nail & KC Remon. tag E. side 44" Oak | S05°E | 61.52' |
| Nail & KC Remon. tag S. side P. Pole | N75°E | 98.69' |
- C/L E-W blacktop is North 4'±



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/6/96