

**SURVEY &
REMONUMENTATION**

KENT COUNTY REMONUMENTATION

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T	8N	R	11W	C-2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 MAR 20 AM 8:52

REG. OF DEEDS

Lucy Stand

9032

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **Kirk Breitels**, in a field survey on **Jan. 19 1996** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1980 KENT COUNTY

PEER APPROVED *3/7/96*

CHAIRMAN *Harrison*

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	●	5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-2	1837	GLO	Whitcomb	Set Post
	1955	Kent Co. Wit.		Stone
	1975	LCRC #823	McCloskey	Stone
	1977	LCRC #971	Hay	Pointed Stone
	1980	LCRC #1434	Merdzinski	Set Kent County Monument
	1994	LCRC #6899	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/21/80 and was recorded per LCRC #1434

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Stone he found. Said Stone checks with Kent Co. Wit. and LCRC #823 & #971.

LCRC #1434 & 6899

Nail & KC Remon. tag NE side 9" Poplar	N80°W	6.54'	Nail & KC Remon. tag
Nail & KC Remon. tag NW side 16" Oak	S38°W	21.22'	SE side 16" Oak N10°E 40.95'
Nail & KC Remon. tag W. side 20" Oak	S20°E	12.35'	Nail & KC Remon. tag
Nail & KC Remon. tag SW side 10" Oak	S60°E	26.79'	SE side 12" Maple N60°E 51.63'
Nail & KC Remon. tag S. side 10" Poplar	N65°E	24.95'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2 Standard Kent County Monument

Nail & KC Remon. tag NE side 9" Poplar	N80°W	6.57'	(dead Poplar)
Nail & KC Remon. tag NW side 20" Oak	S38°W	21.45'	
Nail & KC Remon. tag W. side 24" Oak	S20°E	12.47'	
Nail & KC Remon. tag SW side 16" Oak	S60°E	26.93'	
Nail & KC Remon. tag SE side 20" Oak	N10°E	41.05'	
Nail & KC remon. tag SE side 12" Maple	N60°E	51.63'	
400'± West of Pine Island Dr.			



Signed by *Kirk Breitels*
Surveyor's Michigan License No. **30077**

Date **2/6/96**