

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 8N R 11W

C-7

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

REG. OF DEEDS

Handwritten signature

96 MAR 20 AM 8:54

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9037

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 19, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/2/96

CHAIRMAN *Handwritten signature*

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-7	1837	GLO	Whitcomb	Set Post
		Kent Co. Wit.		1 1/2" Iron
	1975	LCRC #878	Nederveld	Large Iron
	1981	LCRC #2326	Bueche	Set Kent County Monument
	1994	LCRC #6904	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/13/81 and was recorded per LCRC #2326.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" x 36" Solid Rod he found. Said Solid Rod checks with LCRC #878. Kent Co. Wit. are gone.

LCRC #2326 & #6904

Nail & KC Remon. tag E. side 22" Maple	N10°E	16.47'	Nail & KC Remon. tag
Nail & KC Remon. tag NW side 8" Elm	N70°E	27.90'	NW side 12" Maple
Nail & KC Remon. tag NW side 8" Box Elder	N80°W	24.15'	S35°W 60.30'
Nail & KC Remon. tag S. side 12" Elm	S70°W	30.46'	
Nail & KC Remon. tag N. side 12" Maple	S85°W	55.85'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Standard Kent County Monument

Nail & KC Remon. tag E. side 24" Maple	N10°E	16.38'	
Nail & KC Remon. tag NW side 12" Elm	N70°E	27.51'	
Nail & KC Remon. tag NW side 10" Box Elder (clump)	N80°W	23.94'	
Nail & KC Remon. tag N. side 12" Maple	S85°W	55.85'	
Nail & KC Remon. tag NW side 12" Maple	S35°W	60.30'	
Old fence West is North 15'±			
R/W fence South Bd. US 131 is South 100'±			
South Bd. US 131 sta. 609+80 ±			



Signed by *Handwritten signature*

Date 2/6/96

Surveyor's Michigan License No. 30077