

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 27 AM 9:04

For corners in
KENT COUNTY

| (County) | Located In: | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T 8N R 11W | C-11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Lucy J. Bond
REG. OF DEEDS

7900

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on Aug. 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | |
|------|------|---------------|-----------|------------------------------------|
| C-11 | 1831 | GLO | Mullett | Set Post |
| | | Kent Co. Wit. | | No desc. of corner-witnesses given |
| | 1984 | LCRC #3751 | Kolehouse | Set Kent County Monument |
| | 1994 | LCRC #6907 | Byl | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 2/2/84 and was recorded per LCRC #3751

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1/2" Iron he found with stones around. Said Iron checks with previous information by Williams & Works and MDSH and Kent Co. Wit.

| | |
|--------------------------------------|-------------------|
| <u>LCRC #3751</u> | <u>LCRC #6907</u> |
| Nail & tag 12" Ash | N30°W 11.15' |
| Nail & tag 14" Oak | N20°E 7.16' |
| Nail & tag 24" Hickory | N70°E 53.45' |
| Nail & tag 4" Maple | S30°E 14.65' |
| Nail & tag 10" Oak | S55°E 27.80' |
| Nail & tag 3" Ironwood | S55°W 15.37' |
| At remains of fence corner East & NW | |
| same witnesses as LCRC #3751 | |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/22/94
CHAIRMAN *Harry Hubert*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | | |
|------------------------------------|-------------|-------|--------|
| C-11 Standard Kent County Monument | | | |
| Nail & K.C. Remon. tag in SW side | 14" Ash | N30°W | 11.20' |
| Nail & K.C. Remon. tag in W. side | 18" Oak | N20°E | 7.12' |
| Nail & K.C. Remon. tag in N. side | 27" Hickory | N70°E | 53.43' |
| Nail & K.C. Remon. tag in SW side | 4" Maple | S30°E | 14.62' |
| Nail & K.C. Remon. tag in SW side | 12" Oak | S55°E | 27.84' |
| Nail & K.C. Remon. tag in NW side | 3" Ironwood | S55°W | 15.37' |



Signed by *W.R. Byl*
Surveyor's Michigan License No. 23502

Date 12/07/94