

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T8N R11W	D-1
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN [Signature]

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:54
REG. OF DEEDS
[Signature]

9041

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

D-1	1837	GLO	Whitcomb	Not Set
		Kent Co. Wit.		Mon. Box
	1983	LCRC #3462	Bonnema	"T" Iron
	1984	LCRC #4033	Byl	Set Kent County Monument
	1990	LCRC #5652	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 11/7/84 and was recorded per LCRC #4033.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl on Township Line in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wit. and LCRC #3462.

LCRC #4033	LCRC #5652	South	D-13, T9N, R11W
Nail/tag 15" Willow	N30°E 64.13'	32.98'	
Nail/tag 15" Willow	N50°W 108.88'	50.06'	West 428.93'
Nail/tag P. Pole	S20°W 92.52'	S20°W 92.48'	
Nail/tag 12" Maple	S65°E 98.35'	S83°E 172.74'	
Concrete Monument	S00°W 50.03'	N83°E 175.65'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1 Standard Kent County Monument
- 1/2" Pipe
- Concrete Monument
- Nail & KC Remon. tag W. side P. Pole
- Chiseled "X" on bolt S. end 10' x 7' CMP Arch
- Chiseled "X" on bolt N. end 10' x 7' CMP Arch
- Set Nail & KC Remon. tag W. side 18" Willow
- Kent Co. Mon. (D-13, T9N, R11W)

South	32.98'
South	50.06'
S20°W	92.48'
S83°E	172.74'
N83°E	175.65'
N30°E	64.10'
West	428.92'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 3/1/96