

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

	T	8N	R	11W	D-5
	T		R		
	T		R		
	T		R		
S	T		R		
S	T		R		
S	T		R		
S	T		R		

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 18, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1900 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN Harry Huber

A. Description of original monument and accessories and/or subsequent restoration:

D-5	1837	GLO	Whitcomb	Set Post
		Kent Co. Wit.		3/4" Iron
	1974	LCRC #693	Bonnema	3/4" Iron
	1981	LCRC #2267	Bueche	Set Kent County Monument
	1994	LCRC #6911	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10/3/81 and was recorded per LCRC #2267.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #693.

LCRC #2267 & #6911

Nail & KC Remon. tag N. side 26" Pine	S90°W	31.78'	On C/L blacktop N-S S. edge blacktop is S. 38'±
Nail & KC Remon. tag NW side 18" Oak	S60°W	95.62'	
Nail & KC Remon. tag top of guard rail	S06°E	42.15'	
Nail & KC Remon. tag S. side 8" Maple	S90°E	33.23'	
Nail & KC Remon. tag NW side 8" Pine	N40°E	59.97'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Standard Kent County Monument		
Nail & KC Remon. tag N. side 30" Pine	S90°W	31.74'
Nail & KC Remon. tag NW side 24" Oak	S60°W	95.67'
Nail & KC Remon. tag top of guard rail	S06°E	42.15'
Nail & KC Remon. tag S. side 22" Poplar	S90°E	33.17'
Nail & KC Remon. tag NW side 12" Pine	N40°E	59.97'
On C/L blacktop N-S		S. edge blacktop is S. 38'±



Signed by

Kirk Breitels

Date

2/6/96

Surveyor's Michigan License No.

30077

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 MAR 20 AM 8:55  
REG. OF DEEDS  
*Lucy Steward*  
9043  
Register of Deeds Stamp & File Number

