

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>D-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:55
REG. OF DEEDS
Lucy Bond

9044

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN *Harrison*

A. Description of original monument and accessories and/or subsequent restoration:

D-7	1837	GLO	Whitcomb	Set Post
	1964	Kent Co. Wit.		3/4" Iron
	1974	LCRC #731	VanKooten	3/4" Round Iron
	1981	LCRC #2329	Bueche	Set Kent County Monument
	1994	LCRC #6912	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/6/81 and was recorded per LCRC #2329.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" x 18" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #731.

<u>LCRC #2329 & #6912</u>				
Nail/tag 20" Oak	N25°W	55.14'	Rerod in C/L English Ave.	S90°W 19.76'
Nail/tag 18" Box Elder	N60°W	48.00'	E. edge of blacktop is W. 5'±	
Nail/tag 10" Oak	S35°E	20.48'	On fence line W.	
Nail/tag Tw. 8" Oak	N40°E	26.68'	Nail/tag RR tie fence post	S90°W 49.51'
"T" Iron (W & W cap)	East	14.00'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7	Standard Kent County Monument		
	Set Nail & KC Remon. tag NE side 12" Elm	N35°W	59.31'
	Nail & KC Remon. tag W. side 12" Oak	S35°E	20.05'
	Nail & KC Remon. tag NW side Tw. 10" Oak	N40°E	26.81'
	Nail & KC Remon. tag S. side RR tie fence post	S90°W	49.51'
	"T" Iron (W & W cap)	East	13.97'
	Rerod in C/L English Ave.	S90°W	19.76'
	E. edge of blacktop is W. 5'±		
	On fence line W.		



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/6/96